February 23, 2023

SUBJECT: VILLAGE OF HOFFMAN ESTATES

2023 STREET REVITALIZATION PROJECT

REVISED - CLARIFICATION AND RESPONSE TO QUESTIONS

To Whom It May Concern:

This letter is meant to clarify some questions and concerns regarding the 2023 Street Revitalization Project. This is not considered an addendum, but an additional resource for your information and consideration.

- 1. What is required in the pay item POST CONSTRUCTION TELEVISING?

 This pay item consists of televising only new storm sewer, 12" in diameter and up.

 Televising of underdrain, sanitary sewer, or watermain are excluded from this
 pay item and not required for this project.
- 2. How is the callout for CLSM BETWEEN PIPES being paid for?

 At locations specified on pages 49 and 90 in the plan set, CLSM shall be paid per item 20800150 Trench Backfill.
- 3. For pay item HE406440 HMA Surface Removal & Replacement, 2", Special, are the various locations outside the limits of work specified on the plans? Is the quantity designated for one location?

The locations are not identified in the plans and would be outside the limits of reconstruction/resurfacing locations identified on the plans. The quantity is not assumed to be used on one location as exact locations and quantities would be determined in the field by the engineer. Dimensions of the proposed patches will consistent with what is specified in the typical sections.

The above clarifications have been made to assist you in preparing your bid. Thank you for your consideration.

Sincerely,

Andy LoBosco, P.E.

Senior Project Manager